

National Building Codes

Key changes and Northern Construction Considerations

Industry Education and Engagement Session

October 8, 2026 | Whitehorse, Yukon

Updated Oct 15/26

Presented by: Ken Kunka AScT, BCQ

Module 04 – Part 09 Changes

Potential impacts to the Yukon

Information presented does not directly represent the opinions of the Yukon Government or City of Whitehorse.

This presentation is conceptual and for informal educational purposes only. Material presented must not be considered complete or exhaustive. Code provisions have been generally represented and may not reflect all provisions.



FLYWHEEL
BUILDING SOLUTIONS

NBC 2025 Part 9: Focus of this review

This review focuses on the history of **Part 9** and five **significant** changes along with their implications for Yukon's construction industry and occupants.



- **Radon and soil gas mitigation**
- **Lateral Design loads**
 - **climatic & seismic data information changes**
- **Wall studs**
- **Protection from precipitation of rough opening sills**
 - **other window related changes**
- **Technical changes in 9.36 including Energy Performance Tiers**

How will we review the changes

When thinking about a change, we should try to frame it:

Question	Example
What is the Yukon doing now?	Current NBC 2020 vs Yukon practice.
What does the NBC 2025 introduce?	Specific new requirement or clarification?
Is Yukon already partially aligned?	Yes/No
What is the actual gap?	Training, design, supply, inspection, cost, administration
What transition support is needed?	Guidance, phased implementation, exemption

Code Change Review Breakdown

1. Identify the change

Code edition, affected provisions and associated PCFs, where confirmed.

2. Explain the rationale

The problem addressed, the new approach and its practical significance.

3. Consider Yukon application

Local relevance, existing modifications and implementation considerations.

4. Assess potential impacts

Industry and occupants: minor, medium or high, with benefits and challenges.

5. Evaluate adoption options




Education, further review, Yukon modification or a national change request.

6. Recommend next steps

A preferred approach, supporting rationale and outstanding confirmations.

Primary Focus - Code Change Review

Main code reference



**Now Part 2
of NBC**

Parts 9

Referenced documents/standards

Look at Code development & Yukon Regulations
Public Code Reviews (PCFs) – Northern implementation

Part 9: Background and evolution

History and code structure of Part 9

Housing guidance dates to 1950. Part 9 appears in NBC 1970. The objective-based NBC 2005 introduced the Division A/B/C structure. Part 9 now sits in Volume 02 - Division B.

Shared objectives, different scope

Part 9 and Part 3 share the NBC objective framework. Part 9 combines mostly prescriptive rules for housing and small buildings across subjects such as structure, health and energy performance.

Recent code cycles: selected examples

2020: Energy performance tiers, airtightness testing and window safety.

2025: Passive radon stacks, revised structural loads and another compliance path for foamed plastic coverings.

NBC is enforceable only after adoption by AHJ



Part 9 - Housing and Small Buildings



The first formal adoption of the National Building Code in Yukon:

The first formal adoption, which was the 1980 National Building Code of Canada (NBC) (the Eighth Edition) on a territory-wide scale in Yukon occurred with the enactment of the Building Standards Act in 1983.

Yukon current code version

- NBC 2020 with territorial variations (April/23)

Current modification related to Part 9:

- Yukon – [Building Code Modifications Regulations](#)
 - 6 Mobile homes (Z240MH), 7 Modular homes, **7.01 Energy efficiency**
- City of Whitehorse – Building Bylaw No.99-50 – to confirm



Local requirements: Adoption clarifications

Yukon: Building Code Modifications Regulation, s. 7.01

- Clarify the small-home exemption ($\leq 44.6 \text{ m}^2$), attic insulation provision (effective R-40) and crawl-space-floor exception against NBC 2025 Section 9.36.

Whitehorse: Building and Plumbing Bylaw 99-50

- Compare local insulation values, airtightness testing, HRV requirements and EnerGuide labelling with NBC 2025 compliance paths. Confirm nominal versus effective R-values and how crawl-space rules interact.

Confirmation before adoption

- Seek joint clarification from Yukon Building Safety and Whitehorse Building Services on applicable requirements, any amendments and transition rules. Document the agreed interpretation for industry education.

Items for confirmation, not established conflicts with NBC 2025

Radon: 9.13.4. Soil Gas Control - Change rationale

Code references (NBC 2025) - Subsection 9.13.4.

Type of change: Modification and New to the NBC 2020

Existing Yukon modification: NA


Associated PCF - Yes – [PCF 1713, “Passive Vertical Radon Stack,”](#)

Change explanation

- A passive vertical radon stack in dwelling units and home-type care occupancies where a floor assembly separates conditioned space from the ground.
- Sealed overlapping air-barrier seams below concrete slabs, clarified ballast for exposed barriers in heated crawl spaces, and a reference to CAN/CGSB-149.11.

Why it matters

A vented pathway goes beyond a capped rough-in and helps reduce radon exposure. Testing after occupancy remains essential, with further mitigation where needed.



Radon – 9.13.4 Soil Gas Control

New defined term added

9.13.4.1. Application and scope - (1) – ***conditioned space***

Conditioned space means any space within a building, the temperature of which is controlled to limit variation in response to the exterior ambient temperature by the provision, either directly or indirectly, of heating or cooling over substantial portions of the year.

Changes in

9.13.4.2. Protection from Soil Gas Ingress

9.13.4.3. Rough-in for a Subfloor Depressurization System

9.13.4.4. Passive Vertical Radon Stack (required)

Introduction of CAN/CGSB-149.11

How do current building practices work now and how will they need to change?

Will drawings need more detail?



[P29-149-011-2024-eng.pdf](#)

Radon: 9.13.4.2. Protection from Soil Gas Ingress

9.13.4.2. Protection from Soil Gas Ingress

Added

1) All wall, roof and floor assemblies separating a *conditioned space* from the ground shall be provided with an *air barrier system* conforming to Subsection 9.25.3. that provides a level of radon gas diffusion protection equivalent to that provided by 0.15 mm polyethylene sheet conforming to CAN/CGSB-51.34, "Polyethylene sheet for use in building construction – Material specification."

Rewritten

2) Except as provided in Sentence (4), *dwelling units* and *home-type care occupancies* where a floor assembly separates a *conditioned space* from the ground shall be provided with a passive vertical radon stack conforming to Article 9.13.4.4. that is made of components that are compatible with adjoining materials described in Articles 9.13.4.3. and 9.13.4.4.

3) Where *buildings* are used for *occupancies* other than those described in Sentence (2), protection from radon ingress and the means to address high radon concentrations in the future shall conform to

- a) Article 9.13.4.3., or
- b) Parts 5 and 6 (see Articles 5.4.1.1. and 6.2.1.1.).

(See Note A-9.13.4.2.(3).)

New

4) Where an entrance at *grade* contains a floor assembly separating a *conditioned space* from the ground and provides direct access to a stairway leading up to a *dwelling unit* or *home-type care occupancy* located above another *dwelling unit* or *home-type care occupancy*, the entrance and space under the stairway need not comply with Sentence (2).

Introduction of required passive vertical radon stack for all *dwelling units* and *home-type care occupancies*

a stack which runs vertically up through the building and exhausts above the roofline.

with exception of entrance at grade spaces

How do current building practices work now and how will they need to change?
Will drawings need more detail?

Radon: 9.13.4.3. Rough-in for a Subfloor Depressurization System


- 3)** The rough-in referred to in Clause (1)(b) shall include
- clean granular material installed below the floor-on-ground in accordance with Sentence 9.16.2.1.(1), and
 - a pipe not less than 100 mm in diameter installed through the floor, such that
 - its bottom opening is located in the granular layer required in Clause (a) at or near the centre of the floor and not less than 100 mm of granular material projects beyond the bottom opening of the pipe measured along its axis (see Note A-9.13.4.3.(2)(b) and (3)(b)(i)),
 - its bottom opening is protected by a low-pressure-drop stainless steel mesh with 10 mm to 12.5 mm openings or by a product and fitting system that provide an equivalent level of air-flow performance and corrosion resistance,
 - its top opening permits connection to depressurization equipment and is provided with an airtight cap, unless a passive vertical radon stack conforming to Article 9.13.4.4. is connected to the rough-in, and
 - the pipe is clearly labeled near the cap and, if applicable, at every 1.8 m and at every change in direction to indicate that it is intended only for the removal of radon from below the floor-on-ground.

Modified

Modified

Modified

New



Note the capping of the pipe is incorrect for a passive system requirement.



How do current building practices work now and how will they need to change?
Will drawings need more detail?

Radon: 9.13.4.4. Passive Vertical Radon Stack (required)

9.13.4.4. Passive Vertical Radon Stack New Article

(See Note A-9.13.4.4.)

- 1)** The passive vertical radon stack required by Sentence 9.13.4.2.(2) shall be installed
- a) in a *conditioned space* in accordance with Clauses 7.2.2.3 and 7.2.3.2 to 7.2.4.2 of CAN/CGSB-149.11, “Radon control options for new construction in low-rise residential buildings,”
 - b) except as provided in Sentence (2), in the vertical direction, and
 - c) such that its rooftop termination conforms to Table 9.13.4.4.-A.

Note only specific guide references

Table 9.13.4.4.-A
Minimum Clearances for Rooftop Termination of Passive Vertical Radon Stacks
Forming Part of Clause 9.13.4.4.(1)(c)

Description	Minimum Clearance, m
Vertical clearance above the roof at the point of penetration	0.15
Vertical clearance above windows and doors	0.6
Vertical clearance above mechanical air intakes	0.9
Horizontal clearance from windows, doors and mechanical air intakes	3
Clearance horizontally from vertical walls that extend above the penetrated roof	3



Refer also to sentences (2) through (6)

How do current building practices work now and how will they need to change?
Will drawings need more detail?


Radon: CAN/CGSB-149.11

References to CAN/CGSB-149.11.

9.13.4.4. Passive Vertical Radon Stack

- 1) The passive vertical radon stack required by Sentence 9.13.4.2.(2) shall be installed
 - a) In a conditioned space in accordance with **Clauses 7.2.2.3 and 7.2.3.2 to 7.2.4.2 of CAN/CGSB 149.11, “Radon control options for new construction in low-rise residential buildings,”**
- 3) Piping and connections for the passive vertical radon stack
 - a) Shall conform to Clauses 7.1.3.1.1 to 7.1.3.1.3 and 7.1.3.1.5 to 7.1.3.2.6 of **CAN/CGSB-149.11, “Radon control options for new construction in low-rise residential buildings,”**

7.1.3.1.1 Pipes shall have a nominal internal diameter of not less than 100 mm (4 in.)
Should there be a review of nominal size running through the roof (unconditioned space)
– similar to Modification Regulation?



Radon: Yukon impacts

Preliminary qualitative assessment

Industry: Implementation demands

- Additional stack routing and roof penetration require early design coordination.
- Careful air-barrier sealing, flashing and inspection add work and training needs.
- **Confirm cold-climate details for frost, condensation, snow and vent terminal sizing.**
- Plan access for future activation if testing identifies elevated radon.

Industry impact: MEDIUM (mixed)

Occupants: Health protection

- Potential to reduce long-term exposure to a gas associated with lung cancer.
- Protection starts with construction rather than relying only on later retrofits.
- Performance depends on correct installation and follow-up testing.
- Provide owners with testing guidance and next steps if levels remain elevated.

**Occupant impact: HIGH
(positive potential)**



Radon: Adoption and roof-terminal review

Recommended: Education before adoption

- Prepare installation and inspection guidance, plus owner testing information.

Roof-terminal details: Confirmation required

- **Confirm radon sizing, frost protection, clearances and condensate management with Yukon and Whitehorse officials. Check whether Yukon's section 3 plumbing vent provision applies.**

Other options considered

- Further review: Confirm cold-climate radon stack and roof-terminal details.
- Yukon modification or delay: Only for a confirmed gap in radon requirements.
- National Code Change Request: Only for a verified radon design or performance issue.
- No concern for adoption: Support with training and clarified installation details.

Option moving forward: Support adoption with radon guidance and owner testing information. Escalate only confirmed technical or implementation gaps.



Wall studs : Change rationale

Code references (NBC 2025) – 9.23.

Type of change: Modification to the NBC 2020

Existing Yukon modification: NA

Associated PCF 1677

Related CCR 1302

Change explanation

- Revises **Table 9.23.10.1.**, Size and Spacing of Studs, to clarify that 38 mm × 140 mm studs spaced at 400 mm can be used in exterior walls supporting a roof or a roof plus one floor.

Why it matters

This is primarily a clarification of an already common and structurally conservative framing practice, not a new structural requirement. The change removes an apparent gap in Table 9.23.10.1. by expressly recognizing 38 mm × 140 mm studs at 400 mm o.c. in exterior walls supporting:

- a roof, with or without attic storage; or a roof plus one floor.

Wall studs : Change & Recommendation option

NBC 2025

9.23.10.2.

Division B

Table 9.23.10.1. (Continued)

Type of Wall	Supported Loads (including dead loads)	Minimum Stud Size, mm	Maximum Stud Spacing, mm	Maximum Unsupported Height, m
Exterior	Roof with or without attic storage	38 x 64	400	2.4
		38 x 89	600	3.0
		38 x 140	600	3.0
		38 x 140	400	3.6
	Roof with or without attic storage plus one floor	38 x 89	400	3.0
		38 x 140	600	3.0
		38 x 140	400	3.6
	Roof with or without attic storage plus 2 floors	38 x 89	300	3.0
		64 x 89	400	3.0
	Roof with or without attic storage plus 3 floors	38 x 140	400	3.6
		38 x 140	300	1.8

Notes to Table 9.23.10.1.:

(1) See Article 9.23.10.3.

NBC 2020

Exterior	Roof with or without attic storage	38 x 64	400	2.4
		38 x 89	600	3.0
	Roof with or without attic storage plus one floor	38 x 89	400	3.0
		38 x 140	600	3.0
	Roof with or without attic storage plus 2 floors	38 x 89	300	3.0
		64 x 89	400	3.0
	Roof with or without attic storage plus 3 floors	38 x 140	400	3.6
		38 x 140	300	1.8

Notes to Table 9.23.10.1.:

(1) See Article 9.23.10.3.

The clarification benefits designer, builders and building officials.

Option moving forward
LOW IMPACT — ADOPT WITH EDUCATION —
potential cost benefit.

Note - This table addresses stud size, spacing, supported load and height. Confirm lateral bracing, point loads, openings, connections and the complete wall assembly separately.

Designer and inspector checklist update
Cross-reference to Subsection 9.23.13., without implying that stud size establishes braced-wall-panel compliance.



FLYWHEEL
BUILDING SOLUTIONS

Protection from precipitation of rough opening sills

Code references (NBC 2025) – 9.27.2.3 & 9.27.3.

Type of change: Modification & New to the NBC 2020

Existing Yukon modification: NA

Associated PCF - [1950 Protection from Precipitation of the Rough Opening Sills for Windows and Doors](#)

Change explanation

- Clarifies the requirements for protection from precipitation of rough opening sills for windows and doors to improve alignment with established building science principles and standards.

Why it matters

- Improves durability for proper drainage
- Enhances energy efficiency & supports climate change resilience
- Aligns with building science principles



Rough opening sills – change and recommendation

9.27.2.3 (1) First and Second Planes of Protection (NBC 2025)

- ii) effectively dissipate any rain or snow to the exterior, and
- c) the protection provided by the first and second planes of protection shall be maintained
 - i) at the rough opening sills of windows and doors,
 - ii) at wall penetrations for components and services such as ventilation ducts, piping, wiring and electrical outlets, and
 - iii) at the interface with other wall assemblies.

Modified to add rough openings

9.27.3 (1) Second Plane of Protection (NBC 2025)

- 3)** The second plane of protection shall be maintained
 - a) at the rough opening sills of windows and doors in conformance with Sentence (4),
 - b) at wall penetrations for components and services such as ventilation ducts, piping, wiring and electrical outlets, and
 - c) at the interface with other wall assemblies.
- 4)** The protection of rough opening sills required by Clause (3)(a) shall
 - a) conform to Article 9.7.6.1.,
 - b) extend to the interior face of the rough opening sill of the window or door assembly, and
 - c) be constructed of water-impermeable material that
 - i) is liquid-applied or self-adhered, extends up each side of the sill by at least 150 mm, and is securely adhered to the rough opening jambs, or
 - ii) is non-adhesive, where the sheathing membrane of the second plane of protection on the wall face extends into the rough opening to the interior face of the rough opening and down over the non-adhesive sill protection to create a drainage path to the sill.

Expanded

The clarification benefits designer, builders and owner/occupants for improved detailing around openings.

Questions related to drawing requirements and if to be added in inspections as building envelopes are currently not part of typical inspection requirements.


Option moving forward
LOW IMPACT — ADOPT WITH EDUCATION – long term benefits to owner/occupants with more durable and energy efficient window and door installations.

Rough opening sills – change and recommendation


Second Planes of Protection (PCF 1950)

Figure [A-9.27.2.-A]

Rough opening sills - Second plane of protection maintained into the rough opening



Face sealed assembly



Rain-screen assembly



Improper detailing can lead to significant building envelope issues, which can be increased by thicker walls assemblies – see 9.36 outline

RDH

Case Study: Deep Wall with Decayed Sheathing



RDH

Other window/door code changes

Section 9.6 Glass

9.6.1.3. Structural Sufficiency of Glass

Modifications to - Tables 9.6.1.3.-A to 9.6.1.3.-E

- Maximum Glass Area for Windows in Areas for Which the Reference Hourly Wind Pressure (RHWP)

Section 9.7. Windows, Doors and Skylights

9.7.6. Installation

9.7.6.1. Installation of Windows, Doors and Skylights

- 1)** The installation of windows, doors and skylights referred to in Subsections 9.7.4. and 9.7.5. shall conform to CSA A440.4, "Window, door, and skylight installation." **Added**
- 2)** The field assembly of manufactured window and door combination units and the field glazing of windows and doors shall conform to the manufacturer's instructions. **Modified**
- 3)** For protection from precipitation, the *building* envelope at rough openings shall
 - a) allow drainage at sills to prevent damage,
 - b) include protection of sill components, and
 - c) include other details of sill protection that conform to Section 9.27.**New**
- 4)** Windows, doors and skylights shall be sealed to air barriers.

Refer also to changes in 9.36.2.7. later in Module 4.

Article 9.36.2.5. Continuity of Insulation

- | | |
|------------|---|
| New | 12) The rough opening gap around windows and doors, excluding the sill, shall have an effective thermal resistance (RSI value) not less than 0.56 (m ² ×K)/W. (See Note A-9.36.2.5.(12).) |
|------------|---|

Lateral Design Loads

Code references (NBC 2025) – 9.4, 9.23.13, Appendix C climatic and seismic information

Type of change: Modifications and additions to the NBC 2020

Existing Yukon modification: NA

Associated PCFs – [1475 \(ver 1\) Resistance to Lateral Loads](#)

Change explanation

- Updates the seismic design parameter used in Part 9 from $S_a(0.2)$ to S_{max} , adds new prescriptive framing types options for braced wall panels, and extends requirements for bracing to resist lateral loads to locations with low seismic and wind loads.

Why it matters

- The changes to Part 9 lateral design in the NBC are crucial for northern communities due to the increased seismicity and wind loads experienced in these regions. The new requirements aim to enhance the structural resilience of buildings against these environmental hazards, which can lead to significant structural damage or even collapse during extreme events.

Lateral Design Loads

9.4 Structural Requirements

9.4.2.2. Specified Snow Loads **Modified - NBC 2025**

(See Note A-9.4.2.1. and 9.4.2.2.)

1) Except as provided in Sentences (2) to (5), specified snow loads shall be not less than those calculated using the following formula:

$$S = \frac{C_b S_{s,1/1000}}{1.5} + \frac{S_{r,1/1000}}{1.5}$$

where

S = specified snow load,

C_b = basic snow load roof factor, which is 0.45 where the entire width of the roof does not exceed 4.3 m and 0.55 for all other roofs,

$S_{s,1/1000}$ = 1-in-1 000 annual probability ground snow load in kPa, determined according to Subsection 1.1.3., and

$S_{r,1/1000}$ = associated 1-in-1 000 annual probability rain load in kPa, determined according to Subsection 1.1.3.

9.4.2.2. Specified Snow Loads **NBC 2020**

(See Note A-9.4.2.1. and 9.4.2.2.)

1) Except as provided in Sentences (2) to (4), specified snow loads shall be not less than those calculated using the following formula:

$$S = C_b S_s + S_r$$

where

S = specified snow load,

C_b = basic snow load roof factor, which is 0.45 where the entire width of the roof does not exceed 4.3 m and 0.55 for all other roofs,

S_s = 1-in-50-year ground snow load in kPa, determined according to Subsection 1.1.3., and

S_r = associated 1-in-50-year rain load in kPa, determined according to Subsection 1.1.3.

9.4.2.3. Reference Hourly Wind Pressure **New - NBC 2025**

1) The reference hourly wind pressure (RHWP) referred to in this Part shall be calculated as follows:

$$\text{RHWP} = \frac{q_{1/500}}{1.4} \quad \text{NBC 2025 – new reference to wind not previously mentioned in NBC 2020}$$

where

$q_{1/500}$ = 1-in-500 annual probability wind pressure, in kPa, determined in accordance with Subsection 1.1.3.

2) Where the RHWP, as calculated in Sentence (1), is used to design structural members and their connections in accordance with Part 4 and Subclause 9.4.1.1.(1)(c)(i), it shall be multiplied by a factor of 1.4.

9.4.2.6. Seismic Design Parameter **New - NBC 2025**

(See Note A-9.4.2.6.)

1) Except as provided in Sentence (2) and unless otherwise indicated, the value of the seismic design parameter, S_{max} , at a location listed in Table C-3 of Appendix C shall be taken as S_{max} for unknown Site Class. (See Note A-9.4.2.6.(1).)

2) Where the Site Class is determined in accordance with Sentence 4.1.8.4.(3), the value of the seismic design parameter, S_{max} , at a location listed in Table C-3 of Appendix C, is permitted to be taken as S_{max} for the determined Site Class. (See Note A-9.4.2.6.(2).)

3) Where the specified snow load, S , as calculated in Sentence (1) is used to design structural members and their connections in accordance with Part 4 and Subclause 9.4.1.1.(1)(c)(i), it shall be multiplied by a factor of 1.5.

NBC 2025 – note there is a factor error currently being reviewed.

Lateral Design Loads

9.4 Structural Requirements

The introduction of new structural design requirements for snow and wind in the NBC 2025 is a response to the increasing intensity of extreme weather events and the need to ensure the safety and resilience of buildings. The updated code reflects the changing climate patterns, which include increased wind speeds, heavier snowfalls, and more intense thermal loads. These changes are necessary to protect buildings designed to outdated codes (historical data collection) that did not account for these evolving conditions. The new "uniform risk" model for wind and snow loads aims to provide a consistent level of safety across different geographical regions and hazard types, ensuring that structures can withstand the impacts of climate change for the next 75 to 100 years.

For more information review PCF 1475, Appendix C notes, and [New 2025 National Building Code uses future climate data for first time – ClimateData.ca](#)

[Freezing Degree Days | Canada | Climate Atlas of Canada](#)

Lateral Design Loads

Appendix C – Table C-3 Seismic Information

Change Explanation

Updates the seismic design data in Table C-3 used in Part 9 from $S_a(0.2)$ to S_{max}

Table C-3
Seismic Design Parameter, S_{max} , for Selected Locations in Canada

Province and Location	S_{max} for Unknown Site Class	S_{max} According to Site Class				
		A	B	C	D	E
Yukon						
Aishihik	0.906	0.235	0.303	0.564	0.821	0.906
Dawson	0.787	0.245	0.311	0.513	0.721	0.787
Destruction Bay	2.69	1.47	1.89	2.69	2.69	2.08
Faro	0.515	0.141	0.18	0.294	0.452	0.515
Haines Junction	1.3	0.54	0.693	1.06	1.28	1.3
Snag	1.1	0.329	0.427	0.766	1.03	1.1
Teslin	0.567	0.148	0.19	0.322	0.498	0.567
Watson Lake	0.529	0.147	0.189	0.3	0.463	0.529
Whitehorse	0.701	0.171	0.219	0.404	0.619	0.701

NBC 2025

Table C-3
Seismic Design Data for Selected Locations in Canada for Part 9 Design

Province and Location	$S_a(0.2)$ for Seismic Design in Part 9
Yukon	
Aishihik	0.446
Dawson	0.396
Destruction Bay	1.54
Faro	0.271
Haines Junction	0.973
Snag	0.502
Teslin	0.284
Watson Lake	0.304
Whitehorse	0.334

NBC 2020

Lateral Design Loads

Appendix C – Table C-3 Seismic Information

The seismic data in Part 9 of the NBC 2025 was changed from $S_a(0.2)$ to S_{max} to align with the updated seismic hazard values used for design of Part 4 buildings. This change ensures that a single set of seismic hazard values is used for **both Part 4 and Part 9 buildings**, which is crucial for maintaining structural safety and sufficiency. The seismic design parameter, S_{max} , is derived from the 2020 seismic hazard values and is used to design buildings under Part 4 of the NBC 2020.

This update is part of the broader effort to improve design methodologies within Part 9 to address earthquake resistance of housing and small buildings in locations with high seismic hazard values

[For those areas not identified in Table C-3 – go to: 2025 - 2020 National Building Code of Canada Seismic Hazard Tool](#)

Lateral Design Loads


Section 9.23. Wood-Frame Construction

The following is a reference point for changes/additions made within the **NBC 2025** related to lateral design requirements. A more in-depth discussion will be provided later in 2026.


- Modified – 9.20.1 General and 9.20.2. Earthquake Reinforcement
- New – 9.23.2.6. Notation for Reference Framing Types
- New – 9.23.2.7. Weight of Construction and Cladding
- New & Modified – 9.23.3. Fasteners and Connectors
- Modified – 9.23.6. Anchorage
- Modified – 9.23.11 Wall Plates
- **Major revisions and New – 9.23.13. Bracing to Resist Lateral Loads Due to Wind and Earthquake.**
 - 9.23.13.1. Requirements for Low to Moderate Wind and Seismic Forces
 - 9.23.13.2. Requirements for High Wind and Seismic Forces
 - 9.23.13.3. Requirements for Extreme Wind and Seismic Forces
 - Note 9.23.13.7. Simplified Method for Determining Minimum Length of Bracing

Recommend full industry consultation and design review, especially for current unique Yukon building practices


Lateral Design loads : Resources



CHBA Tech Essentials



CHBA Backgrounder



Based on NBC 2025 with modifications

Part 9 – Lateral Design

Challenges/Industry Impacts

- Significant modifications and additions for industry to review.
- Impacts to communities outside of Whitehorse with additional snow loads.
- Anchorage for buildings on permafrost without traditional foundations
- Additional concerns with current building practices (double frame walls and S406 PWF, and external insulation.
- Some areas within 9.23.13. under review.

Benefits to the Communities/Occupants

- Improved safety for occupants.
- Opportunity for increased consistency in design, construction and permitting processes.

**Moving forward: Consider full industry review prior to adoption.
Escalate if major gaps identified.**




9.36 Energy Efficiency

Today's code change session on Energy Efficiency will mainly revolve on discussing technical changes and possible impacts to the building industry and Yukon community.

Additional time can be provided today to expand on the issues related the questions on which energy tier should the Yukon select.

We encourage you to participate in the engagement process and ensure you read the reports prepared by Andrew Pride Consulting.

See <https://engageyukon.ca/national-building-code-engagement>



9.36.1.3. Compliance Options - Energy Efficiency

9.36.1.3. Compliance

- 1)** Except as provided in Article 9.36.1.4. and Sentences (3) and (4), *buildings* shall comply with
- a) the prescriptive or trade-off requirements in Subsections 9.36.2. to 9.36.4.,
 - b) the performance requirements in Subsection 9.36.6.,
 - c) the NECB, or
 - d) for compliance with Energy Performance Tiers 1 to 5,
 - i) the tiered performance requirements in Subsection 9.36.7.,
 - ii) the tiered energy use intensity requirements in Subsection 9.36.8.,
 - iii) the tiered points-based prescriptive trade-off requirements in Subsection 9.36.9.,
 - iv) the tiered prescriptive path requirements in Subsections 9.36.10. to 9.36.14., or
 - v) the NECB.
- 2)** Except as provided in Article 9.36.1.4. and Sentences (3) to (5), *buildings* shall comply with
- a) the tiered operational GHG emissions performance requirements in Subsection 9.36.15.,
 - b) the tiered operational GHG emissions prescriptive requirements in Subsection 9.36.16., or
 - c) the NECB.
- 5)** Extensions added to *existing buildings* that have a *floor area* not greater than 60% of the original gross *floor area* of the *existing building* are exempted from the requirements of Subsections 9.36.15. and 9.36.16.

9.36.1.2. Definitions - New

- 9)** For the purposes of this Section, the term “house” shall mean all houses, with or without a *secondary suite*, that
- a) have HVAC systems that serve only the house, only the *secondary suite*, or both the house and the *secondary suite*,
 - b) have service water heating systems that serve only the house, only the *secondary suite*, or both the house and the *secondary suite*, and
 - c) do not share common spaces intended for occupancy with other *dwelling units* or houses, except for a *secondary suite*.

9.36 - 1. Thermal characteristics of fenestration and doors

Code references (NBC 2025) – 9.36.2.7.

Type of change: Modification to the NBC 2020

Existing Yukon modification: NA

Associated PCF 1823



Change explanation

Places an upper limit on the solar heat gain coefficient for fenestration and doors that depends on the fenestration and door area to gross wall area ratio (FDWR) and the climate zone of the building location.

Why it matters to the North

- Encourages better management of overheating from large window areas
- Balance winter solar gains with summer comfort (is this a problem here?)

9.36 - 1. Thermal characteristics of fenestration and doors

Challenges/Industry Impacts

- More coordination between designers and window suppliers – how will this be enforced?
- Less flexibility to use large areas of high-solar gain glazing.
- Additional design calculations may be required.

Benefits to the Communities/Occupants

- Reduced overheating risk.
- Improved occupant comfort.
- Potentially lower cooling demand.

Observation – even though the Yukon does not experience extreme summer temperatures, prolonged sun exposure throughout the day during the summer months may have a negative impact to occupants

Moving forward: Consider adoption with ongoing education and review within larger 9.36 discussions. Escalate if major gaps identified.



9.36 - 2. Tiered Energy Compliance: Energy Use Intensity Path

Code references (NBC 2025) – 9.36.8.

Type of change: NEW to the NBC 2020

Existing Yukon modification: to confirm

Associated PCF 1869

Change explanation

Introduces an optional energy use intensity path in which compliance with the energy performance tiers is demonstrated by meeting an annual energy consumption target, an annual gross space heat loss target, and a design cooling load budget and that recognizes the inherent energy savings of smaller and more compact housing forms.

Why it matters for North

- Recognizes the efficiency advantages of compact housing forms
- Provides an alternative to the traditional reference-house approach.

9.36 - 2. Energy use intensity path

Challenges/Industry Impacts

- Requires energy modelling expertise.
- New compliance process for builder and permit reviewers.
- Additional documentation requirements.

Benefits to Communities/Occupants

- Encourages lower-energy homes.
- Supports more housing design flexibility
- May reduce long-term operating costs.

Moving forward: Consider adoption as an optional compliance pathway.



9.36 - 3. Tiered Energy Compliance: Points-based Prescriptive Trade-off Path

Code references (NBC 2025) – 9.36.9.

Type of change: Modification to the NBC 2020

Existing Yukon modification: NA

Associated PCF 1838 along with 1923, 2000, 2001

Change explanation

- Revises the optional energy conservation measures, and corresponding points, available in the prescriptive trade-off path for demonstrating compliance with the energy performance tiers, including updates related to drain-water heat-recovery units, oil- and gas-fired furnaces, air-source heat pumps, heat/energy recovery ventilators, the building envelope, airtightness, and fenestration and doors.
- Sets the minimum sums of energy conservation points required for compliance with Energy Performance Tiers 3, 4 and 5.

Why it matters for the north

- Expands options for meeting energy targets.
- Recognizes newer technologies and equipment.

9.36 - 3. Points-based prescriptive trade-off path

Challenges/Industry Impacts

- Learning curve for revised points systems.
- More product comparisons and design decisions.
- Additional permit reviewer training required.

Benefits to Communities/Occupants

- More efficient equipment choices
- Better building performance.
- Opportunity for innovation without one prescribed solution.

Moving forward: Likely option to adopt.





9.36 - 4. Tiered Energy Compliance: Tier 01 & Tier 05

Code references (NBC 2025) – 9.36.10 to 9.36.14.

Type of change: **New to NBC 2020**

Existing Yukon modification: unsure

Associated **PCF 2042 - Tier 1 PCF 1830, Tier 5 PCF 2043**

Change explanation

Provides an optional simple set of prescriptive energy efficiency requirements for demonstrating compliance with Energy Performance Tiers 1 and 5.

Why it matters to the north

- Provides a straightforward “recipe-book” compliance option
- May be attractive where modelling resources are limited.



9.36 – 4.Prescriptive compliance for Energy Performance Tiers

Challenges/Industry Impacts

- Less design flexibility.
- Prescriptive packages may not suite every project type.
- Higher tiers may increase material and equipment costs

Benefits to Communities/Occupants

- Easier compliance process.
- Greater consistency from project to project. (this may be good for modular)
- Better certainty regarding expected performance

Moving forward: could be strong candidate for Yukon implementation.

9.36 - 5. Operational greenhouse gas emissions

Code references (NBC 2025) – 9.36

Type of change: **New to NBC 2020**

Existing Yukon modification: **NA**

Associated **PCF 2004 & 2026**



Change explanation

Introduces both performance and prescriptive requirements, within a framework of gradually increasing reduction levels, to establish limits for operational greenhouse gas emissions resulting from the supply and consumption of energy used by the building, as determined at the time of design.

Why it matters to the north

- Introduces carbon-emissions considerations in addition to energy efficiency.
- May influence future decisions on heating systems and fuel choices.



9.36 - 5. Operational greenhouse gas emissions

Challenges/Industry Impacts

- New compliance concepts and metrics.
- Potential impacts on equipment selection.
- Regional energy-supply differences may affect implementation.

Benefits to Communities/Occupants

- Supports climate objectives
- Encourages lower-emission buildings
- May improve long-term sustainability of the housing stock.

Moving forward: Conduct Yukon specific evaluation before adoption.

9.36 Yukon Implementation Lens



The changes create three distinct implementation questions to discuss during the ongoing engagement process:

- **Technical:** Are the new paths and prescribed measures appropriate for northern climate and construction?
 - Are there other related code requirements that should be considered, such building envelopes (9.27) and lateral design (9.23)
- **Capacity:** Are energy advisors, designers, suppliers, builders and officials prepared to apply and verify them?
- **Policy:** Which energy and GHG tiers should Yukon adopt, and on what transition schedule?



9.36 Building Envelope Concerns

With the increased use of higher energy efficiency assemblies (thicker walls), there is a growing concern related cooler exterior faces of walls that can be negatively impacted by deficient cladding details allowing moisture to enter and the thicker assemblies are not able to “dry” as with older assemblies - leading to potential for rot. Here are some examples provided by RDH deep wall case study.




9.36 Yukon Implementation Lens

The main shift in thinking in the Yukon as we discuss this important topic, is the main shift is not simply toward “more insulation”. It is toward more:

- compliance options,
- more explicit performance targets,
- and a stronger evidence trail connecting design assumptions to the completed building.

Connecting plans, energy reports and field application through an integrated design and consultation process.



Part 9 summary and next steps

Topics reviewed

- Radon and soil gas mitigation
- Lateral loads
- Wall studs
- Protection from precipitation of rough opening sills
- Energy Performance Tiers - technical changes in 9.36

Possible next steps

- Confirm code references, unresolved PCFs and Yukon application.
- Prepare targeted education and worked examples.
- Test Yukon designs and gather community and industry feedback.
- Document technical gaps before proposing code modifications.



Webinar sessions – October 20th and 27th.

Question or Comments



Contact Us

If you have questions about process, or want to share your feedback directly, contact us.

Contact Information

Email nbc.engagement@yukon.ca